



PROPOSED SIDE ELEVATION




PROPOSED SIDE ELEVATION

MATERIALS -


Constructed from pre-cast machine-vibrated steel re-enforced concrete panels, with spar pebbledash exterior finish
Each unit complete with 1no Hormann steel horizontal rib up-and-over garage door in white finish
White uPVC fascias and trims
Galvanised box-profile steel sheeted roof, with non-drip lining, supported on galvanised steel C-section purlins
uPVC guttering and downpipes



PROPOSED REAR ELEVATION



PROPOSED FRONT ELEVATION



PROPOSED STORAGE UNITS PLAN

This drawing and its contents are the copyright of Belmont Design and must not be used, reproduced or amended without prior consent from such.

This drawing is not a working drawing, and is only for the purpose of the following -

- A - Planning Submission
- B - Building Regulations Submission

The main contractor is responsible for informing Belmont Design of any discrepancy on, or between, this drawing and any other related document.

All existing walls, foundations and lintels or other structural items are to be confirmed load bearing and adequate for increased loading where relevant prior to work commencing.

Any existing walls to be removed are to be confirmed non-loadbearing prior to removal.

Boundaries, angles, and dimensions are to be checked by the main contractor prior to work commencing.

Written dimensions only to be used from this drawing - if doubt exists consult Belmont Design for clarification.

NOTE

Client please note that you have duties under the CDM 2015

Main contractor to provide a pre-construction information and health and safety file to help them comply with their duties, such as ensuring a construction phase plan PDF is prepared.

Main contractor to reduce or remove any foreseeable health and safety risks to anyone affected by the project (if possible) and to take steps to reduce or control any risks that cannot be eliminated

CDM Contractor is to ensure stability of existing structure throughout the works

Contractor to note heavy elements, specifically steel beams.

PLEASE NOTE THAT BELMONT DESIGN SERVICES HAS BEEN APPOINTED TO DEAL WITH THE INITIAL DESIGN STAGE AND IS NOT INVOLVED IN THE PRECONSTRUCTION PHASE



BELMONTDESIGN services ltd
TEL : 01274 690586

ARCHITECTURAL SERVICES
231 High Street Wibsey, Bradford. BD6 1QR
www.belmontdesign.co.uk

PROPOSED STORAGE UNITS AT :

Land to rear 74 to 76 Acre Avenue
Bradford
BD2
(grid ref 417751 436207)

FOR :
Mr Carmelo Gangeri and Mr David Toffoli

Proposed Plan
Proposed Elevations

Date - June 2024

Scale - 1:50

Dwg No. - 10149/03